

## **Top 10 Sign Turndowns**

1. Incomplete permit applications, drawings, and/or site plans.
2. No permit prior to sign installation.
3. Unlicensed contractor and/or employees.
4. Not calling for proper inspections by contractors.
5. Insufficient footings and structures.
6. Not meeting setback requirements.
7. Improper or no labeling of electric signs (third party, manufacturer, volts, amps, and lamps ) as required by Article 600 of the National Electrical Code.
8. No disconnects and improper spacing for neon, also insufficient bonding.
9. Failure to remove temporary signs after expiration of permit.
10. Attempting to permit signs that (a) exceed sign area, (b) exceed total number of allowable signs (freestanding), and/or (c) exceed height requirements.