Stormwater Best Management Practices

 $\mathsf{M} \quad \mathsf{A} \quad \mathsf{N} \quad \mathsf{U} \quad \mathsf{A} \quad \mathsf{L}$

Stormwater Best Management Practices Manual

Prepared for:
City of Chattanooga

Prepared by:
P.E.Yakimowich, PE
ComQuest, LLC
2689 Churchill Downs Cir
Chattanooga
Tennessee 37421
Tel 423 505 5359
p-ey@worldnet.att.net

Ref.: 96-51024-02

Date: March 2000

Table of Contents

1.	Purpose, Applicability, and Scope				
2.	BMP Guidelines				
3.	Erosi	Erosion and Pollution Control Plan			
BMP Specifications 4.7					
	4.1	Check Dam	4.1		
	4.2	Channel Stabilization	4.4		
	4.3	Construction Exit	4.9		
	4.4	Diversion	4.11		
	4.5	Temporary Downdrain Structure	4.16		
	4.6	Gabion	4.19		
	4.7	Rock Filter Dam	4.23		
	4.8	Retrofitting	4.26		
	4.9	Sediment Barrier	4.30		
	4.10	Inlet Sediment Trap	4.37		
	4.11	Portable Sediment Tank	4.40		
	4.12	Temporary Sediment Basin	4.42		
	4.13	Temporary Stream Crossings	4.53		
	4.14	Storm Drain Outlet Protection	4.56		
	4.15	Surface Roughening	4.61		
	4.16	Topsoiling	4.66		
	4.17	Vegetated Waterway or Stormwater Conveyance Channel	4.69		
	4.18	Buffer Zone	4.75		
	4.19	Disturbed Area Stabilization (with Mulching Only)	4.76		
	4.20	Disturbing Area Stabilization (With Temporary Seeding)	4.79		
	4.21	Permanent Seeding	4.82		
	4.22	Disturbed Area Stabilization (Sodding)	4.88		
	4 23	Dust Control on Disturbed Areas	4 93		

c\marshalltemplbmpmanualredolbmp manual-pey.doc

Table of Contents

Tables

	4.4.1	Diversion Design Criteria
	4.4.2	Permissible Velocities and Retardant Values for Vegetated and Rock-Lined Waterways
	4.5.1	Pipe Diameter for Temporary Downdrain Structure
	4.7.1	Graded Riprap Stone
	4.9.1	Criteria for Sediment Barrier Placement
	4.9.2	Silt Fence Types
	4.9.3	Post Sizes
	4.9.4	Fasteners for Wood Posts
	4.9.5	Silt Fencing Specifications
	4.13.1	Pipe Diameters for Stream Crossings
	4.17.1	Permissible Velocities and Retardant Values for Vegetated Waterways
	4.17.2	Velocity, Top Width and Depth for Parabolic Stone Center Waterways
	4.21.1	Seeding Mixtures, Rates and Dates
	4.23.1	Emulsion Application Rates
Figur	es	
	4.1.1	Stone Check Dam Installation Requirements
	4.1.2	Straw Bale Barrier Installation Requirements
	4.3.1	Crushed Stone Construction Exit Installation Requirements
	4.3.2	Geotextile Liner Under Gravel Pad
	4.4.1	Typical Diversion Across Road
	4.5.1	Temporary Downdrain and Inlet Detail
	4.7.1	Rock Filter Dam Installation Requirements
	4.8.1	Perforated Half-Round Pipe Retrofit With Stone Filter
	4.8.2	Perforated Half-Round Pipe Retrofit With Stone Filter Installation Requirements
	4.8.3	Slotted Board Dam Installation Requrements
	4.9.1	Straw Bale Barrier Installation Requirements

c:\marshalltemplbmpmanualredolbmp manual-pey.doc

Table of Contents

4.9.2	Use Type "A" Silt Fence
4.9.3	Use Type "B" Silt Fence
4.9.4	Type "C" Silt Fence
4.9.5	Typical Type "C" Silt Fence
4.10.1	Fabric and Supporting Frame for Inlet
4.11.1	Siltsack
4.12.1	Components of a Typical Temporary Sediment Basin
4.13.1	Temporary Stream Crossing Installation Requirements
4.13.2	Typical Sediment Basin Trash Rack
4.13.3	Concrete Riser Base Detail
4.15.1	Stair-Stepping Cut Slopes
4.17.1	Typical Vegetated Waterway or Stormwater Conveyance

Appendices

- A Chattanooga Stormwater Management Ordinances
- B Chattanooga Landscape Ordinance
- C Participating Local Community Stormwater Ordinances

c\marshalltemplbmpmanualredolbmp manual-pey.doc